


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Mark
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

STAFFORD County. Sec 8 Twp. 21S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner NADEL & GUSSMAN
Lease Name BARRETT Well No. 1
Office Address 625 UNION CENTER - WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) XXX WASHDOWN
Date well completed _____ 19____
Application for plugging filed OCTOBER 7 19 69
Application for plugging approved _____ 19____
Plugging commenced OCTOBER 7 19 69
Plugging completed OCTOBER 11 19 69
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. WARREN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3679' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	867'	NONE
				5 1/2"	3679'	1966.67'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3679' - 3639' PLUG
 3639' - 3490' SAND
 3490' - 3450' 5 SACKS CEMENT
 3450' - 275' MUD
 275' - 265' ROCK BRIDGE
 265' - 190' 25 SACKS CEMENT
 190' - 40' MUD
 40' - 30' ROCK BRIDGE
 30' - BASE 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1969
CONSERVATION DIVISION
Wichita, Kansas

10-23-69

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SANTA FE PIPE & SUPPLY, INC.
Address BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. Nutt (employee of owner) or ~~Know or Operate~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 69

My commission expires JULY 31, 1970
Mary M. Guesnier
Mary M. Guesnier Notary Public.

WELL LOG

Jayhawk Drilling

Barrett No. 1

NE SE NW 8-21S-14W
Stafford County, Kansas

Comm:
Comp: 2-5-54

Casing: 8-5/8" cemented to surface

Anhydrite	885
Shale and Shells	1450
Shale and Lime	3200
Lime	3260
Lime and Shale	3680

Geological Tops

Viola	3578
Simpson	3610
Arbuckle	3654

Well was Plugged and Abandoned on 2-5-54

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1969

CONSERVATION DIVISION
Wichita, Kansas

Nadel and Gussman & Aspen Drilling Co.

Comm: 3-22-69
Comp: 6-5-69

Casing: 8-5/8" cemented to surface
5-1/2" 3679' 125 sacks

Washed well down, Set 5-1/2", tested Lansing, to be plugged and abandoned.

STATE OF OKLAHOMA

COUNTY OF TULSA

M. R. Taylor, of lawful age, states that the above formations and depths are correct to his best knowledge and beliefs.

M R Taylor

Subscribed and sworn to before me this 19th day of August, 1969.

Mildred Carter
Notary Public

My commission expires May 11, 1971.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company-JAYHAWK DRILG.
Farm- Barrett

No. 1

SEC. 8
NE SL NW


T. 21

R. 14W

Total Depth. 3680'
Comm. 1-20-54
Shot or Treated.
Contractor.
Issued. 7-3-54

Comp. 2-2-54

County Stafford
KANSAS



CASING:
8 5/8" 867' w/400 sx cem.

Elevation. 1935 RB

Production. Dry

Figures indicate Bottom of Formations.

surfcae soil-sand-shale	160
shale-shells	400
sand	500
red bed	863
Anhydrite	890
red bed-shale-shells	1285
shale-shells	1380
shale-salt	1540
lime-shale	3063
lime	3101
lime-shale	3226
shale blk	3230
lime	3234
shale	3239
lime	3256
shale	3329
lime	3335
shale	3339
lime	3543
lime-shale	3578
chert	3610
shale-sdy shale	3658
chert-shale	3662
dolomite	3680
Total Depth	

TOPS: Scout	
Toronto	3239
Douglas	3256
Lansing	3339
Viola Chat	3578
Simpson	3610
Arbuckle	3659

DST-3666-3680-good blow, open
20 min, Rec. 2160' wtr. FP 215#-
954# SFP 1163# 15 min.

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1969
CONSERVATION DIVISION
Wichita, Kansas