


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Worth

Pawnee County, Sec. 30 Twp. 23 Rge. 15 (West)(W)
Location as "NE/CNW&SW¼" or footage from lines S½ SW ½
Lease Owner Robert L. Austin
Lease Name Benson Well No. 4
Office Address Box 159, Stafford, Kansas 67578
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 1/3/53 19____
Application for plugging filed Called in 19____
Application for plugging approved yes 19____
Plugging commenced 5/31/84 19____
Plugging completed 4/4/84 19____
Reason for abandonment of well or producing formation Junk In Hole
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation Arbuckle Depth to top 4145 Bottom 4245 Total Depth of Well 4245 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle				8 5/8		None
				5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5/31/84 Allied cementing pumped 75 sacks cement, one sack of hulls. Dwon 5½, closed back side, pumped 25 sacks cement, mixed 4 sacks of gel, pressure increased to 200 pounds. Pumped 100 sacks cement down 5½ at 200 pounds pressure. Shut in 5½ casing, pumped 100 sacks of cement between 8 5/8 and 5½ casing. At the end of pump period pressure 100 pounds.
6/4/84 Returned to location with pressure truck. Cement was down six feet in 5½, took less than ½ barrel between 8 5/8 and 5½ casing. Pressured well to 200 pounds, held pressure okay.
Back filled and cleaned up location

RECEIVED
STATE CORPORATION COMMISSION
6-12-84 JUN 12 1984
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing
Address Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Stafford, ss.
Owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 159, Stafford, Kansas 67578
(Address)

SUBSCRIBED AND SWORN to before me this 12 day of June, 1984
BILLIE POSTIER
NOTARY PUBLIC
Stafford County, Kansas
MY APPOINTMENT EXPIRES February 21, 1988

Billie Postier
Notary Public.

My commission expires February 21, 1988