

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

A 4x4 grid with a small cross in the center.

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3450' Feet
Show depth and thickness of all water, oil and gas formations.

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

3450'	-	301 $\frac{1}{2}$ '	-	Heavy Rotary Mud
301 $\frac{1}{2}$ '	-	300'	-	Wooden Plug
300'	-	254'	-	15 sacks cement
254'	-	31 $\frac{1}{2}$ '	-	Heavy Rotary Mud
31 $\frac{1}{2}$ '	-	30'	-	Wooden Plug
30'	-	6'	-	10 sacks cement
6'	-	Surface	-	Cellar

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1951 4-26-51

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Peel-Hardman
Address P. O. Box 359, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Glenn W. Peel (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
GLENN W. PEEL

BY: Glenn W. Peel
(Signature) Herbert

P. O. Box 359, Hoisington, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of April, 1951

My commission expires.

PLUGGING
FILE SEC 21 T 16 R 122
BOOK PAGE 75 LINE 75

8-50--10M

Notary Public.

15-009 - 00377 - 00-00

DRILLER'S LOG

Company: Peel-Hardman

NE NW SE

Sec. 21 Twp. 16S Rge. 12W

Farm: Stoskopf Well No. 1

Comm: 4-8-51 Comp: 4-18-51

County: Barton,

Kansas

Total Depth: 3450'

Contractor: Glenn W. Peel

Elevation:

Casing:

8 5/8" 304' cem.

Production: Dry

Figures below indicate bottom of formations

Surface Clay	0 -	40
Shale & Shells		186
Sand		214
Shale & Shells		266
Sand		291
Shale		304
Shale & Shells		820
Anhydrite		855
Shale & Shells		1518
Lime		1595
Lime & Shale		1750
Lime		2015
Lime w/shale streaks		2155
Lime & Shale		2275
Shale w/lime streaks		2435
Shale & Lime		2750
Lime & Shale		2820
Lime		3000
Lime & Sandy Shale		3125
Lime		3420
Arbuckle		3450
Total Depth		3450

This is to certify that the above information is, to the best of our knowledge true and correct.

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1951
CONSERVATION DIVISION
Wichita, Kansas

GLENN W. PEEL

BY: Manaw M. Herbert

SUBSCRIBED AND SWORN to before me this 24th day of April, 1951.

My commission expires June 4, 1951

Manaw M. Herbert
Notary Public

PLUGGING
FILE SEC-21-T-16R-12W
BOOK PAGE-75 LINE-25