

15-009-03329-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Barton County, Sec. 21 Twp. 16 Rge. (E) 12 (W)
Location as "NE/CNW/SE" or footage from lines 77' E SE SW SE
Lease Owner Duke Drilling Company
Lease Name Stoskopf #4 Twin Well No. _____
Office Address Box 823, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed January 8 19 60
Application for plugging filed May 13 19 69
Application for plugging approved _____ 19 _____
Plugging commenced May 20 19 69
Plugging completed May 27 19 69
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3387 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-------|--------|--------|------------|
| | | 0 | 327' | 8 5/8" | 327' | none |
| | | 0 | 3385' | 5 1/2" | 3385' | 2516.96 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back from 3387' to 3320'. Mixed and dumped 5 sacks of cement.

Pushed plug to 300', set 10' rock bridge from 300' to 290'. Mixed and dumped 5 sacks of cement on bridge at 290'. Bailed hole down and dumped 20 sacks of cement on bridge at 285'. Filled hole with mud to 40', set 10' rock bridge and capped hole with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1969
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 4th day of June, 19 69

My commission expires December 1, 1969



15-009-03329-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1969
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Date Commenced
Date Completed

December 29, 1959
January 8, 1960

Stoskopf #4 Twin
77' East SE SW SE
Section 21-16-12
Barton County, Kansas

| | |
|---------------|--------------------|
| 0' - 30' | Surface Clay |
| 30' - 38' | Part Rock |
| 38' - 210' | Sand & Shale |
| 210' - 325' | Shale & Shells |
| 325' - 555' | Shale & Clay |
| 555' - 812' | Red Bed |
| 812' - 842' | ANHYDRITE |
| 842' - 1855' | Shale & Shells |
| 1855' - 2500' | Shale & Lime |
| 2500' - 2815' | Lime & Shale |
| 2815' - 2987' | Lime |
| 2987' - 2991' | Shale HEEBNER |
| 2991' - 3007' | Lime & Shale |
| 3007' - 3019' | Lime TORONTO |
| 3019' - 3079' | Shale DOUGLAS |
| 3079' - 3096' | Lime Shale - IATAN |
| 3096' - 3346' | Lime Shale LANSING |
| 3346' - 3366' | CONGLOMERATE |
| 3366' - 3387' | Dolomite ARBUCKLE |
| | RTD |

Elevation 1920' KB

| | | |
|--------------|-------|-------|
| Anhydrite | 812' | 1108 |
| Topoka | 2714' | - 794 |
| Heebner | 2987' | -1067 |
| Toronto | 3007' | -1087 |
| Douglas | 3019' | -1099 |
| Iatan | 3079' | -1159 |
| Lansing | 3096' | -1176 |
| Conglomerate | 3346' | -1426 |
| Arbuckle | 3366' | -1446 |
| RTD | 3387' | -1467 |

Surface Casing: 327' of 8 5/8" set with 190 sacks
Production Casing: 3385' of 5 1/2" set with 100 sack common cement 200 gal. ratex.

AFFIDAVIT

State of Kansas County of Barton

I, Lewis O. Chubb, Geologist, do swear that the statements and matters herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

By: L. O. Chubb
Geologist

Subscribed and sworn to before me this 11th day of January, 1960

Clair E. Stinson
Notary Public

My Commission Expires: June 24, 1963