


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 21 Twp. 16S Rge. 12 (#) (W)
Location as "NE/CNW/SW" or footage from lines SW/4 SW/4 NW/4
Lease Owner John Jay Darrah
Lease Name Stoskopf Well No. 2
Office Address 303 South Main, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed July 30 1956
Application for plugging filed July 30 1956
Application for plugging approved July 30 1956
Plugging commenced July 30 1956
Plugging completed July 30 1956
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Depth to top Bottom Total Depth of Well 3439 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 330 feet. Set wooden plug at 330 feet. Dumped one-half sack of hulls and 20 sacks of cement on plug and completed filling with heavy mud to 40 feet. Set second plug at 40 feet. Dumped one-half sack of hulls and 10 sacks of cement on plug to fill to bottom of cellar

8-3-56

STATE CORPORATION COMMISSION
AUG 3 1956

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Building, Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick contractor, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. R. Stubblefield
409 First National Bank Bldg.
Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st. day of August, 1956

My commission expires February 27, 1960

Mildred F. Willis
Notary Public.

PLUGGING

FILE SEC 21 T 16 R 12W
BOOK PAGE 85 LINE 25

15-009-05945-00-00

BARNETT DRILLING, INC.
LOG OF STOSKOPF WELL NO. 2
SW/4 SW/4 NW/4 SECTION 21-16S-12W
BARTON COUNTY, KANSAS.

Commenced: 7/21/56

Completed: 7/30/56

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	-0-	40	Set 8-5/8" Casing at 370 feet; Cemented with 200 sacks.
Sand	40	60	
Post Rock	60	80	
Shale	80	370	
Shale	370	410	
Shale and Shells	410	830	
Anhydrite	830	860	
Shale and Shells	860	1770	
Shale	1770	1910	
Shale and Lime	1910	2035	
Lime	2035	2150	
Shale and Lime	2150	2285	
Shale	2285	2650	
Shale and Lime	2650	2800	
Lime	2800	2975	
Lime and Shale	2975	3085	
Lime	3085	3439	
Total Depth		3439	Dry and abandoned

CERTIFICATE

I, F. R. Stubblefield of Barnett Drilling, Inc. certify that to the best of my knowledge and belief, that the foregoing is a true and correct log of the Stoskopf Well No. 2 located in the SW/4 SW/4 NW/4 of Section 21-16S-12W, Barton County, Kansas.

F. R. Stubblefield

Subscribed and sworn to by and before me in and for the County of Sedgwick, State of Kansas, this 2nd. day of August, 1956.

Mildred F. Willis

My commission expires February 27, 1960.

AUG. 2 1956
 CONSERVATION

PLUGGING

FILE SEC 21 T. 16 R. 12W
 BOOK 85 LINE 25