


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 35 Twp. 21 Rge. (E) 14 (W)

Location as "NE/CNWxSWx" or footage from lines SE NW SE
Lease Owner Chief Drilling Co., Inc.
Lease Name Kennan Well No. 1
Office Address P. O. Box 97, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 12 19 59
Application for plugging filed April 13 19 59
Application for plugging approved 19
Plugging commenced April 12 19 59
Plugging completed 1:45 A.M. April 12 19 59
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	-0-
<p>RECEIVED STATE CORPORATION COMMISSION APR 16 1959 CONSERVATION DIVISION Wichita, Kansas</p>						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug set with 20 sacks cement, 1/3 sack hulls @250'

Second plug set with 10 sacks cement, 1/3 sack hulls @35'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF BARTON, ss.
V. Richard Hoover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard Hoover
P. O. Box 97, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1959

Mary O Johnson
Notary Public.

My commission expires November 21, 1959

PLUGGING
FILE SEC. 35 T. 21 R. 14w
BOOK PAGE 31 LINE 15

WELL LOG

Chief Drilling Co., Inc.
P. O. Box 97
Great Bend, Kansas

No. 1 Keenan
SE NW SE Sec. 35-21-14W
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.
Rotary: 0 - 3845' T.D.

Commenced: March 31, 1959
Completed: April 12, 1959

Casing Record: 253' of 8-5/8" surface casing with 200 Pozmix cement. Cement Circulated.

DRY AND ABANDONED

Figures Indicate Bottoms of Formation

Sand	0	225	
Shale	225	300	
Red Bed	300	370	
Shale and Red Bed	370	430	
Sand	430	475	
Shale and Shells	475	700	
Red Bed and Sand	700	856	
Anhydrite	856	878	
Shale	878	1180	
Shale and Shells	1180	1700	
Lime and Shale	1700	1825	
Lime, Shale and Iron	1825	1845	
Lime and Shale	1845	3205	
Lime	3205	3240	
Lime	3240	3790	
Simpson Shale	3790	3815	
Arbuckle	3815	3845	T.D.

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1959
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
County of Barton) S.S.

I hereby certify that the above is a true and correct copy of Driller's Log of well drilled in the SE NW SE of Section 35, Township 21 South, Range 14 West, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 13th day of April, 1959.

PLUGGING
FILE SEC. 35 T. 21 R. 14W
BOOK PAGE 31 LINE 15

Mary O. Johnson
Mary O. Johnson, Notary Public