

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Stafford County. Sec. 35 Twp. 21 Rge. 14 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. N/2 S/2 SW/4

Lease Owner Petroleum, Inc.

Lease Name Matzek Well No. #2

Office Address 100 Derby Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 6, 1951

Application for plugging filed February 6, 1951

Application for plugging approved February 8, 1951

Plugging commenced February 6, 1951

Plugging completed February 6, 1951

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3430 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	245'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Wooden plug set at 240'. Cemented and displaced through drill pipe 15 sax. Filled hole with heavy mud to 30'. Placed wooden plug at 30'. Filled hole to surface with 10 sax cement.

RECEIVED  
STATE CORPORATION COMMISSION  
2-13-51 FEB 13 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.  
Address 100 Derby Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Eric H. Jager (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager

100 Derby Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of February, 1951

Charlotte Heidman  
Notary Public.

My commission expires October 13, 1954

PLUGGING  
FILE SEC 35 T 21 R 14  
BOOK PAGE 60 LINE 38  
23-8273-5 4-60-10M

WELL LOG MATZEK #2

Petroleum, Inc., Lease Owner

Section 35, Twp. 21, Rge. 14W

Garvey Oil, Contractor

Location: C. N/2 S/2 SW/4

Rotary Total Depth: 3430'

County: Stafford, Kansas

Commenced: January 29, 1951

Production: D & A

Completed: February 6, 1951

Elevation: 1940 D.F.

Casing: 245' of 8 5/8"

Figures below indicate bottom of formation:

175 Sand & Shale  
 245 Shale & Shells  
 820 Red Rock  
 830 Gyp.  
 855 Anhydrite  
 1280 Shale & Shells  
 1830 Lime  
 1990 Lime & Shale  
 2395 Shale & Shells  
 2865 Lime & Shale  
 3145 Lime  
 3331 Lime & Shale  
 3430 Shale

Tops  
 3296 Heebner  
 3319 Toronto  
 3420 Brown Lime  
 3429 Lansing

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 FEB 13 1951  
 CONSERVATION DIVISION  
 Wichita, Kansas

3430' R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

*Eric F. Jago*

STATE OF KANSAS:  
 : SS.  
 SEDGWICK COUNTY:

Subscribed to and sworn to before me, a Notary Public in said County and State this 12th day of February, 1951.

*Charlotte Waldman*  
 Notary Public

My commission expires: 10-13-54

**PLUGGING**  
 FILE SEC. 35 T. 21 R. 14W  
 BOOK PAGE 60 38