

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-185-23133-0000
LEASE NAME Rexroad/Ferguson
WELL NUMBER 1-16

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2310 Ft. from South Line of Section
2310 Ft. from West Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION Ne Ne Sw
ADDRESS P.O. Box 780167 Section 16 Township 21s Range 14w
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Stafford
PHONE # 316-684-8481 Date Well Completed August 30, 2001
Character of Well Dry and Abandoned Date Plugging Commenced August 30, 2001
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed August 30, 2001

The plugging proposal was approved on August 29, 2001 at 1:30 pm (date)
by Steve Pfeifer (KCC District Agent's Name)
Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3875

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	125			
Redbeds	Shale	125	450	8-5/8"	446.46'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well on 8/30/01 using 165 sx 60/40 Poz, 6% Gel, as follows: Heavy mud in the hole.

Bottom plug @ 3762' with 40sx, 2nd plug @ 886' with 50sx, 3rd plug @ 470' with 50sx

and top plug @ 30' with 10sx cemented to surface, Plugged rathole with 15 sx. Job completed

at 4:00 am on 8/30/01 by Acid Services, ticket #3828.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature)

Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)


(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 31st day of August, 2001

RECEIVED

SEP 04 2001 9-4-01

KCC WICHITA



Pamela S. Fields
(Notary Public)

My Commission Expires: _____

al

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG**Rexroad/Ferguson 1-16**

LOCATION: Ne Ne Sw Section 16 T 21s R 14w
API: 15-185-23133-0000 Stafford County, Kansas

OWNER: F.G. Holl Company, L.L.C.
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 22-Aug-01
COMPLETED: 30-Aug-01

TOTAL DEPTH: **DRILLER** 3875 FEET
LOGGER 3874 FEET

Ground Elevation: 1933
KB Elevation: 1942

LOG

0 -	3 FEET	Top Soil
3 -	8 FEET	Clay
8 -	17 FEET	Fine sand
17 -	53 FEET	Sand and Gravel
53 -	125 FEET	Clay
125 -	450 FEET	Sand and Shale
450 -	853 FEET	Redbeds
853 -	860 FEET	Anhydrite (Driller's)
860 -	1320 FEET	Redbeds, Shales and Salt
1320 -	3762 FEET	Limestone, Shale and Dolomite
3762 -	3875 FEET	Arbuckle

CASING RECORDS**Surface Casing-8-5/8"**

Spud @ 10:00 am on 8/22/01. Drilled 12-1/4" hole to 450'. Ran 11 joints of new 23# 8-5/8" surface casing, tally 446.56' set at 442' KB. Cemented with 350 sx 60/40 Poz, 2% Gel, 3% CC and 1/4# Celloflake. Cement did circulate. Plug down at 2:00 am on 8/23/01 by Acid Services.

Plugging Report

Plugged well on 8/30/01 using 165 sx 60/40 Poz, 6% Gel, as follows: Heavy mud in the hole. Bottom plug @ 3762' with 40sx, 2nd plug @ 886' with 50sx, 3rd plug @ 470' with 50sx and top plug @ 30' with 10sx cemented to surface, Plugged rathole with 15 sx. Job completed at 4:00 am on 8/30/01 by Acid Services, ticket #3828.

DEVIATION SURVEYS

1	degree(s) at	450	feet
1-1/2	degree(s) at	3430	feet
1-1/4	degree(s) at	3730	feet
1-1/4	degree(s) at	3875	feet

RECEIVED

SEP 04 2001

KCC WICHITA