

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 16 Twp. 21 Rge. 14 W

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE-SE-SE

Lease Owner Petroleum, Incorporated

Lease Name Bayer Well No. 1

Office Address 100 Derby Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 5, 19 51

Application for plugging filed January 3, 19 52

Application for plugging approved January 26, 19 52


Plugging commenced January 17, 19 52

Plugging completed January 26, 19 52

Reason for abandonment of well or producing formation Depletion of producible zones

If a producing well is abandoned, date of last production November 9, 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Kansas City Depth to top 3558' Bottom 3566' Total Depth of Well 3762' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	small show oil	3747'	3748'	8-5/8" OD	232'	none
Lansing	Oil	3558'	3566'	5-1/2" OD	3760'	3,025'
Lansing	Water	3525'	3531'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

(Baker Cast Iron plug set at 3,550' top.) Filled hole with sand and chet from 3550' to 3515', and placed 5 sacks cement on top of sand and chet at 3515'. Filled hole with heavy mud to 275'. Placed wooden plug at 275' and pumped 85 sacks cement into surface casing completely filling pipe and one foot in well cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Rural Route 2  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF ~~Stafford~~ SEDGWICK, SS.  
Paul B. Shivel (employee of owner) or (owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul B. Shivel  
R.F.D. 2, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of February, 19 52

Charlotte Fairman  
Notary Public.

My commission expires October 13, 1954

PLUGGING  
FILE SEC 16 T 21 R 15 W  
BOOK PAGE 135 LINE 30

FEB 9 X 1952  
2-9-52

WELL LOG DAYER #1

Petroleum, Inc. & Dooley Engineering Co.

Section 16, Twp. 21S, Rge. 14W

Contractor: Garvey Oil

Location: SE SE SE

Rotary Total Depth: 3762'

County: Stafford, Kansas

Commenced: April 13, 1951

Elevation: 1939 K.B.

Completed: April 27, 1951

Casing: 226' of 3 5/8"  
3761' of 5 1/2"

Figures below indicate bottom of formation:

20 Surface Soil  
200 Sand & Clay  
226 Blue Shale & Shells  
325 Shale  
856 Red Bed  
885 Anhydrite  
1120 Shale & Shells  
1360 Shale, Salt & Shells  
1575 Shale & Shells  
1825 Lime & Shale  
1925 Lime  
2872 Lime & Shale  
2905 Shale & Shells  
3125 Lime & Shale  
3266 Lime  
3294 Shale  
3371 Lime & Shale  
3620 Lime  
3651 Lime & Shale  
3662 Chert  
3699 Lime & Shale  
3742 Shale  
3762 Lime

Tops:

856 Anhydrite  
3266 Heebner  
3290 Toronto  
3382 Brown Lime  
3294 Lansing  
3626 B.K.C.  
3651 Cong.  
3656 Viola  
3694 Simpson  
3742 Arbuckle

DST #1, 3509-25, open 1 hr., rec. 50' muddy water, BHP 950#  
DST #2, 3534-64, open 1 hr., rec. 180' oil cut mud, 60' heavily oil cut mud, BHP 910#  
DST #3, 3575-3620, open 3/4 hrs., rec. 30' mud, BHP 0#  
DST #4, 3743-46, open 1 1/2 hrs., rec. 110' heavy black oil cut mud to muddy oil, 60' sulphur water, BHP 1010#

3762' R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

**PLUGGING**  
FILE SEC 46T 21 R 16W  
BOOK PAGE 135 LINE 3e  
SS.

STATE OF KANSAS:

SEDFWICK COUNTY:

FEB 27 1951  
*Eric H. Jager*  
Eric H. Jager

Subscribed to and sworn to before me, a Notary Public in said County and State this 2nd day of May, 1951.

My commission expires: 10-13-54

*Charlotta Heedman*  
Notary Public