

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 16 Twp. 21S Rge. 14 XXXXX (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner D. R. Lauck Oil Company, Inc.

Lease Name Bayer Well No. 1

Office Address Wichita Kans

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed January 26 19 57

Application for plugging filed January 26 19 57

Application for plugging approved January 26 19 57

Plugging commenced January 26 19 57

Plugging completed January 26 19 57

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage

Producing formation --- Depth to top _____ Bottom _____ Total Depth of Well 3795 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	867	8 5/8"	867	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

filled hole with mud 3796- 180
plug 180- 176
cement 176- 136
mud 136- 45
plug 45- 41
cement 41- 6 bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1957

CONSERVATION DIV.
Wichita, Kans.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Company

Address Great Bend Kans

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John H. Knightley (employee of owner) of ~~KANSAS OIL COMPANY~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
Wichita Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 31 day of January, 19 57

My commission expires Sept. 14, 1959

Elizabeth Gay
 Notary Public.

PLUGGING
 FILE SEC 16.121 R.14W
 BOOK PAGE 136 LINE 41

D. R. Lauck Oil Company, Inc.

Bayer #1

SW SW SE Sec.16-21S-14W
Stafford County, Kansas

Commenced: January 15, 1957

Completed: January 26, 1957

Casing Record: 867' 8 6/8" cem. with 425 sacks

Elevation: GR 1935; DF 1937; KB 1939;

Drillers LogTops

sand and clay	205	Anhydrite (Drillers)	859+ 1080
blue shale	290	Brown Lime	3409- 1470
sand	380	Lansing Kansas City	3420- 1481
shale & red bed	625	Base Kansas City	3655- 1716
shale, red bed & shells	859	Conglomerate	3677- 1738
Anhydrite	890	Viola	3697- 1758
shale & shells	1715	Simpson Shale	3740- 1801
shale & Lime	1785	Simpson sand	3752- 1813
lime & shale	2315	Arbuckle	3777- 1838
shale & shells	2775	Rotary Total Depth	3795- 1856
lime & shale	2990		
lime	3275	DST #1 (W) 3622-3652	open 30 min; weak blow
shale & lime	3330		9 min; recovered 25' mud; BHP 160# 20 min.
shale	3409		
lime	3715	DST #2 (W) 3698-3725;	open 45 min. weak
Viola	3752		blow 18 min; recovered 65' mud
sand	3760		BHP 400# in 30 min.
lime & shale	3777		
Arbuckle	3795	DST #3 (W) 3753-3760	open 1 hr;
rotary total depth	3795		fair steady blow 1 hr. recovered 155'
			salt water BHP 840# in 30 min.

D & A

RECEIVED
STATE CORPORATION COMMISSION

FEB -2 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE	SEC. <u>16</u> T. <u>21</u> R. <u>14W</u>
BOOK	PAGE <u>136</u> LINE <u>41</u>