

KANSAS

JP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued July 12, 1967.

Operator's Full Name Circle Oil Company, Inc.

Complete Address 500 Bitting Bldg., Wichita, Kansas 67202

Lease Name Williams Well No. # 1

Location NW NW NW Sec. 16 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3549'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221, Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 11:30 P.M. Day 26th Month July Year 1967

The above well was plugged as follows:

275' of 8 5/8" surface pipe, cement circulated. 3543' of 5 1/2" long string,
cemented with 100 sacks. This is an open hole. Bottom of the hole was sanded
to 3500', and cemented with 5 sacks, through the dump bailer, from 3500' to
3460'. 2790' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 260', bridge plug and rock bridge from 260' to 250'. 10
sacks of cement was mixed in a barrel, and put on plug at 250', through the
dump bailer, and let set over-night. Next day hole was bailed dry, and 15
sacks of cement was added to the plug, with cement from 250' to 175'. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sack
to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 7/28/67
INV. NO. 6032-W