

15-185,00365,000 1

Form CP-3  
Rev. 6-26-62

*W*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Duke Drilling Company

Complete Address: P. O. Box 823, Great Bend, Kansas

Lease Name Laudick "C" Well No. # 2

Location E/2 W/2 E2 Sec. 10 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3540

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: This hole had been Washed Down

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 12:00PM Day 17th Month June Year 1964

The Above well was plugged as follows:

241' of 8 5/8" surface pipe, cement circulated. 3539' of 4 1/2" long string,  
cemented with 600 gallons of Latex. Plug back to 3420'. Top perferation  
3485'. Bottom of the hole was sanded to 3475', and cemented with 3 sacks.  
Hole was squeezed. 15 sacks of Gel-Mud and 75 sacks of cement was pumped  
into surface pipe, through and 8 5/8" swage, to a pressure of 400 lbs.  
A wiping plug was run between the Gel-Mud and the cement. This cementing  
was done by Forbes Casing Pulling Inc.

3230' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/19/64  
INV. NO. 9237-11

15.185-00365-0001

The Laudick "C" 2 Washdown is the same as the Laudick "B" 1,  
drilled in September, 1959.

The Duke Drilling Company is the Operator for both wells.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1964

CONSERVATION DIVISION  
Wichita, Kansas