

15.185.30319.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name F.G. Holl

Complete Address 6427 E. Kellogg Wichita, KS

Lease Name Ben Kasselmann B Well No. 1

Location SE/SE/NE Sec. 12 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3430

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc

Address Box 486 Ellinwood, KS License No. 462

Operation Completed: Hour 4:00 PM Day 11 Month 8 Year 1973

The above well was plugged as follows:

251 ft 8 5/8 surface cemented with 250 sacks. 3429 ft 4 1/2 long string
cemented with 75 sacks. Top perf. 3318 ft. Sand to 3290 ft, 4 sacks
cement with bailer. Pulled 2500 ft 4 1/2. Pump 2 sacks hulls, 10
sacks gel, 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8/15/73
INV. NO. 4765-W