

**KANSAS**  
**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

MAR 6 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Intent to Drill, filed  
February 27, 1967.

Operator's Full Name F. G. Holl

Complete Address: 6427 East Kellogg, Wichita, Kansas

Lease Name Gilchrest Well No. # 1

Location SE SE SW Sec. 12 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3432'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Duke Drilling Company

Address: Box 823, Great Bend, Kansas License No.     

Operation Completed: Hour 8:45AM Day 4th Month March Year 1967

The Above well was plugged as follows:

253' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid  
level in the hole was at 110', 1st cementing plug and 1/2 sack of hulls  
was pushed in fluid to 230', and cemented with 25 sacks at 230'. Hole  
was filled with drilling mud to 40', 2nd cementing plug, bridged with  
1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base  
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Aubie Elving  
Well Plugging Supervisor

DATE 3/7/67  
INV. NO. 4858-W