

15-43-19053-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 E. Broadway
Wichita, Kansas

Pawnee

County. Sec. 30 Twp. 23 Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE 1/4

Lease Owner M. B. Armer

Lease Name Hall A Well No. 1

Office Address 710 Petroleum Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas Well

Date well completed December 1952

Application for plugging filed February 15 1957

Application for plugging approved February 15 1957

Plugging commenced February 15 1957

Plugging completed February 23 1957

Reason for abandonment of well or producing formation Well depleted

If a producing well is abandoned, date of last production Dec. 14 1956

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4125 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	295	None
				5 1/2	4106	1731.85

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Run 5 sacks of cement at 4000 ft
Mudded to 255 ft.
Set rock bridge to 240 ft.
Run 20 sacks of cement at 240 ft
Mudded to 30 ft.
Set rock bridge to 25 ft.
Run 10 sacks of cement to cap.

Name of Plugging Contractor C. E. Shull, Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
L. C. Sponenberg

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. C. Sponenberg*

SUBSCRIBED AND SWORN to before me this 12 day of March, 19 57

My commission expires Feb. 13, 1960

Notary Public. *Rose Fussey*
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 30 T. 23 R. 15W
BOOK PAGE 141 LINE 11

MAR 14 1957 3-14-57
CONSERVATION DIVISION
Wichita, Kansas

LOG

15-K5-19053-0000

Company: M. B. Armer
Contractor: M. B. Armer (Unit Rig)
Drilling Commenced: 12-4-52
Drilling Completed: 12-17-52
Elevation: 2050 K.B.

Farm: Hall #1
Location: SW SW SE
Sec. 30-23S-15W
Pawnee County, Kans.
Casing Record: 8-5/8" casing at
295' with 185 sacks.
5 1/2" casing at 4106

(figures below indicate bottoms).

Sand	190
Shale	295
Sand & Surface Clay	450
Sand	505
Red Bed & Shale Sand	955
Anhydrite	980
Red Bed, Shells, Salt	1350
Shale & Shells	1750
Lime & Shale	1900
Lime	2248
Shale & Lime	2760
Shale	2900
Lime & Shale	3515
Shale & Shells	3605
Shale & Lime	3645
Lime	3890
Lime & Shale	3950
Lime	3980
Shale & Lime	4090
Lime	4125
R.T.D.	4125

FORMATION TOPS (R.B. Meas.)

HEEBNER	3497
BROWN LIME	3629
LANSING-KANSAS CITY	3639
SIMPSON	4062
ARBUCKLE	4106

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

By L. L. Spaulding

RECEIVED
STATE OF KANSAS COMMISSION
FEB 14 1957
ss. _____
COUNTY OF SEDGWICK

STATE OF KANSAS

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 31st day of December, 1952.

Hayden Dalton
Notary Public

My Commission Expires: Sept. 17, 1955.

PLUGGING
FILE NO. 30 T. 23 R. 15W
BOOK PAGE 141 LINE 11