

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1  
 SW NE SW Ft. from S Section Line  
 \_\_\_\_\_ Ft. from E Section Line

LEASE OPERATOR Berexco, Inc.  
 ADDRESS Box 723 Hays, Kansas 67601  
 PHONE# (785) 628 6101 OPERATORS LICENSE NO. 5363

SEC. 30 TWP. 23S RGE. 15W (E) or (W) (W)  
 COUNTY Pawnee  
 Date Well Completed 1/4/53  
 Plugging Commenced 3/16/2000  
 Plugging Completed 3/27/2000

Character of Well Oil  
 (Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 3/27/2000 (date)  
 by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4052

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	350	8 5/8		
	Casing	0	4078	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.  
 Cement at 1390'. Perf. at 1000'. Pump down 5 1/2 no blow on 8 5/8. Mix 150 sk. 60/40 pos 2 1/2 jell with 2% calcium. Disp. to 700' Shut in at 350' Let set 45 min. Perf. at 500' 2 SPF. Pump 125 sk. 60/40 2% gel, 2% cal. Circulation on 8 5/8. Did not circulate. Shut in 100#. Tag cement at 178'. Top off and tie onto annulus. Mix 30 sk. 60/40 and fill 5 1/2 casing to surface. Hook to 8 5/8 and mix 30 sk. 60/40 and fill annulus.

Name of Plugging Contractor Berexco, Inc. License No. 5363  
 Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BEREXCO, Inc.  
 STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Mark Leiker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

NOTARY PUBLIC - STATE OF KANSAS  
 ROSEMARY SMITH  
 My Appl. Exp. 5-10-2003

(Signature) Mark Leiker  
 (Address) Box 723 Hays, Kansas 67601

RECEIVED STATE CORPORATION COMMISSION SUBMISSION AND SWORN TO before me this 12 day of April 19 2000

APR 12 2000  
 My Commission Expires: \_\_\_\_\_  
 CONSERVATION DIVISION  
 Wichita, Kansas

Rosemary Smith  
 Notary Public

Form CP-1  
 Revised 05-88