

API NUMBER 15-185-22979-0000

LEASE NAME ROSE

WELL NUMBER #1

2310' Ft. from S Section Line

2310' Ft. from E Section Line

SEC. 16 TWP. 21 RGE. 12 (X30 or (X))

COUNTY STAFFORD

Date Well Completed 11-16-94

Plugging Commenced 4:00 AM

Plugging Completed 8:30 AM

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR GLOBE OPERATING, INC.

ADDRESS P O BOX 12

PHONE(S) 316 792-7607 OPERATORS LICENSE NO. 6170

Character of Well _____

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-13-94 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? no if not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.O. 3676'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	28 1/2" 29 1/2"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from _____ feet to _____ feet each set

Heavy mud to 3540' (top of Arbuckle is 3542'), 40 sacks at 3540', 50 sacks at 670', 50 sacks at 330', 10 sacks at 40' to surface. 15 sacks in rathole. Used 60/40 Pozmix with 6% gel.

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P. O. Box 129, Sterling, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Globe Operating, Inc.

STATE OF KANSAS COUNTY OF RICE, ss.


11-22-94

Richard L. Mead (Employee of Operator) or (Operator)

I, above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Richard L. Mead NOV 22 1994

(Address) P. O. Box 129, Sterling, KS 67579



SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 94

Cheryl B. Davis
 Notary Public

My Commission Expires: 02-15-97

USE ONLY ONE SIDE OF EACH FORM

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- ROSE #1

Located: 2310' FSL & 2310' FEL NW NW SE Sec. 16-21S-12W,
Stafford County, Kansas

OWNER: GLOBE OPERATING, INC.

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: November 10, 1994

COMPLETED: November 16, 1994

TOTAL DEPTH: 3676' Driller
3677' Logger

LOG

0' - 190' Surface Soil and Sand
190' - 305' Red Bed
305' - 650' Red Bed - Shales
650' - 1525' Clay and Shale
1525' - 3550' Shale and Lime
3550' - 3560' Dol.
3560' - 3676' Arbuckle

CASING RECORD

Spud at 7:30 AM, 11-10-94. Drilled 305' of 12 1/4" hole. Ran 8 joints 8 5/8" surface casing. 287.37' set at 296' K.B. Cemented with 200 sacks of 60/40 Poz mix with 2% gel, 3% cc. Plug down at 12:00 Noon 11-10-94 by Allied, ticket #1146. Good returns.

Plugged.

DEVIATION SURVEY

2 1/4° @ 3550'

2 1/2° @ 3676'

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1994

STATE CORPORATION COMMISSION
WICHITA, KANSAS