


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 16 Twp. 21 Rge. 12 (E) (W)
Location as "NE/CNW/SW" or footage from lines. NW NW NW
Lease Owner Circle Oil Company, Inc.
Lease Name Williams Well No. 1
Office Address 500 Bitting Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 7-7-67 19____
Application for plugging approved 7-8-67 19____
Plugging commenced 7-10-67 19____
Plugging completed 7-26-67 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3549 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 275 | None |
| | | | | 5 1/2 | None | 2805 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar. Sanded to 3500'. Dumped 5 sacks of cement. Worked pipe.
Working pipe. Shot pipe at 2890'.
Working pipe. Circulating. Spotted 65 bbl of oil.
Working pipe. Shot pipe at 2790'.
Working pipe. Pulling pipe.
Pulling pipe. Pushed plug to 260' rock bridge. Dumped 10 sacks of cement.
Bailing hole dry. Dumped 15 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

STATE CORPORATION COMMISSION
JUL 31 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of July 19 67

My commission expires May 27, 1969

Notary Public.

DRILLERS LOG

No. 1 Williams


| | | | |
|-----------------------------------|--------------------|------------------------|---|
| CASING RECORD: | COMPANY: | Circle Oil Company | DESCRIPTION: |
| 8 5/8" @ 329' w/275 sz cement | CONTRACTOR: | Red Tiger Drilling Co. | SE NW 16-218-12W Stafford Co., Kans. |
| 5 1/2" @ 3549' w/125 sz cement | COMMENCED: | September 21, 1964 | ELEVATION: 1871 DF 1874 BB |
| TOTAL DEPTH: 3550' | COMPLETED: | September 29, 1964 | |

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|-----------------------|-------------|-----------|----------------|
| Sand & Shale | 0 | 230 | |
| Shale | 230 | 330 | |
| Shale & Redbed | 330 | 668 | |
| Anhydrite | 668 | 697 | |
| Shale Shells & Redbed | 697 | 1495 | |
| Shale & Lime | 1495 | 2368 | |
| Shale & Shells | 2368 | 2645 | |
| Shale & Lime | 2645 | 3010 | |
| Lime | 3010 | 3550 | |


RECEIVED
 STATE CORPORATION COMMISSION
 JUL 12 1967
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY


 Maxine V. Head

Subscribed and sworn to before me this 2nd day of October, 1964.


 Notary Public

My Commission Expires:
5-22-69

