


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plot

Stafford County, Sec. 11 Twp. 21 Rge. (E) 12 (W)

Location as "NE/CNW&SW&" or footage from lines NW NW NE  
Lease Owner Larry G. Stephenson  
Lease Name Holl Well No. 1  
Office Address 340 Farm Credit Banks Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil 67202  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced Nov. 23 19 73  
Plugging completed Nov. 29 19 73  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 3487 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	292'	8 5/8"	292'	none
		0	3443'	4 1/2"	3443'	2548.55

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3420' and dumped 4 sacks of cement.

Sun Cementing Company plugged well pumping in 2 sacks of hulls, 10 sacks of mud and 100 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC.  
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON ss.  
Evelyn Roth (employee of owner) or (owner-or-operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December 19 73

My commission expires Feb. 10, 1975

George A. Meyer Notary Public

DRILLERS LOG

No. 1 Well

**CASING RECORD:**

8 5/8" @ 292'  
w/275 sx cement

4 1/2" @ 3443'  
w/100 sx cement

**TOTAL DEPTH: 3487'**

**COMPANY:**

L. V. Stan Bell

**CONTRACTOR:**

Red Tiger Drilling Company

**COMMENCED:**

September 10, 1970

**COMPLETED:**

September 18, 1970

**DESCRIPTION:**

NW NW NE  
11-21S-12W  
Stafford County,  
Kansas

**ELEVATION:**


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	180	
Red Bed & Shale	180	615	
Anhydrite	615	632	
Shale & Shells	632	1400	
Lime & Shale	1400	2846	
Lime	2846	3049	
Haebner	3049	3053	
Lime	3053	3075	
Shale, Douglas	3075	3183	
Lime	3183	3193	
Lansing	3193	3195	
Lime	3195	3445	
Lime, Shale, Sand	3445	3487	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Jim Farrice*  
Jim Farrice

and sworn to before me this 21 day of September, 1970.



*Virginia K. Allect*  
Notary Public

My Commission Expires:

July 23, 1974

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 27 1973  
CONSERVATION DIVISION  
Wichita, Kansas