


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 10 Twp. 21 Rge. 12 (E) (W) X

Location as "NE/CNW/SW" or footage from lines E 1/2 W 1/2 E 2

Lease Owner The Duke Drilling Company

Lease Name Laudick "C" Well No. 2

Office Address P. O. Box 823 Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 6-11-64 19

Application for plugging approved 6-12-64 19

Plugging commenced 6-13-64 19

Plugging completed 6-17-64 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie W. Elving

Producing formation Depth to top Bottom Total Depth of Well 3540 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	241	None
				4 1/2	None	3256'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar.

Rigged up jacks. Measured T. D. Mudded to 2400'.

pumping mud out. Measured T. D. Sanded to 3180' and 3 sacks of cement.
Shot pipe at 3230'.

Pulled 21 joints of pipe. Pipe froze.

Spotted 40 bbl. of oil.

Pulled rest of pipe.

Plugging well. Squeezed with 75 sacks of cement and 15 sacks of mud.

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1964

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. O. Forbes
P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of June, 1964

My commission expires May 27, 1965

Notary Public.

WELL LOG

Date Started September 18, 1959
Date Completed September 29, 1959

LANDICK "C" 2
Laudick "B" # 1
80' N. of C. E/2 W/2 E/2
Section 10-213-12W
Stafford County, Kansas

Elevation	1846	KB
Anhydrite	595'	1251'
Heebner	3065'	1219'
Toronto	3084'	1238'
Douglas	3099'	1253'
Iatan	3198'	1352'
Lansing	3212'	1366'
Simpson	3433'	1587'
Arbuckle	3487'	1641'
RTD	3533'	1687'
Surface Casing	8 5/8" @	241'

0'	-	208'	Surface Sand
208'	-	241'	Red Beds
241'	-	595'	Red Beds
595'	-	624'	Anhydrite
624'	-	795'	Shale & Shells
795'	-	1495'	Shells & Shale
1495'	-	1640'	Shale & Lime
1640'	-	1861'	Lime & Shale
1861'	-	2130'	Lime & Shale
2130'	-	2500'	Shale & Lime
2500'	-	2835'	Lime & Shale
2835'	-	3065'	Lime
3065'	-	3069'	Shale - Heebner
3069'	-	3075'	Lime
3075'	-	3084'	Shale
3084'	-	3098'	Lime - Toronto
3098'	-	3198'	Shale - Douglas
3198'	-	3212'	Lime, Shale - Iatan
3212'	-	3433'	Lime, Shale, - Lansing
3433'	-	3487'	Shale - Simpson
3487'	-	3533'	Dolomite Arbuckle
3533'			Rotary T.D.

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1964

CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

State of Kansas County of Barton

I, Lewis O. Chubb, employee of the owner, do swear that the statements and matters herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

By: Lewis O. Chubb

Subscribed and sworn to before me this 30th day of September, 1959.

Clay E. Stinson
Notary Public

My Commission Expires: June 24, 1963