



Name: Laudick NW NW SE Section 10-21S-12W, Stafford County, Kansas  
 Company: Virginia Drilling Company, Inc. & E. H. Adair  
 Contractor: Virginia Drilling Company, Inc.  
 Commenced: April 10, 1947  
 Completed: April 25, 1947  
 Total depth: 3552  
 Elevation: 1846

<u>FORMATION</u>	<u>DEPTH</u>	<u>TOPS:</u>	
sand	0- 250	Heebner sand	3070
Shale	250- 625	Brown Lime	3209
Anhydrite	625- 665	Kansas City	3222
Shale-shells	665-1200	Base of KC	3442
Salt-shells	1200-1375	Top Arbukel	3501
Lime-shale	1375-1505		
Lime	1505-1795		
Lime-sand	1795-1910		
Lime	1910-1975	CIRCULATE:	
Lime-shale	1975-2165	1 hr @ 3505	
Lime	2165-2265	1 3/4 hr @ 3508	
Lime-shale	2265-2735	2 hrs @ 3513	
Lime	2735-2788		
Lime, sandy, soft	2788-2820	Set 8 5/8" csg @ 308	
Lime, hard	2820-2972		
Lime	2972-3020		
Lime, broken	3020-3075		
Lime	3075-3223		
Lime-shale	3223-3239		
Lime, dark	3239-3250		
Lime, light	3250-3446		
Lime	3446-3470		
Shale	3470-3499		
Shells	3499-3505		
Lime	3505-3552 TD		
Arbukole			

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and known of his own knowledge that the Laudick located in the NW NW SE section 10-21S-12W, Stafford County, Kansas, was drilled to a total depth of 3552 feet. Same was plugged and abandoned.

Subscribed and sworn to before me, a Notary Public, this 30<sup>th</sup> day of April, 1947.

My commission expires: February 1, 1949.

