


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 EXating Building  
Wichita, Kansas

NORTH



Locate well correctly on above Section Flat

Stafford County. Sec. 10 Twp. 21 Rge. 12 (E) (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NE SW  
Lease Owner Marko Dizdar Investment Company  
Lease Name Christiansen Well No. 1 B  
Office Address Box 194, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 10, 1951 1951  
Application for plugging filed June 10, 1951  
Application for plugging approved June 16, 1951  
Plugging commenced June 10, 1951  
Plugging completed June 10, 1951  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production..... 19.....  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough M.A. Rives  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3601 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	227'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Filled hole with heavy mud to 210', set plug, dumped 15 sacks wet cement thru drill pipe. Second plug set at 40'. Dumped 10 sacks wet cement and filled to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 16 1951  
CONSERVATION DIVISION  
WICHITA, KANSAS  
6-16-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Duke & Wood Drilling Company, Inc.  
Address P. O. Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Cecil M. Olson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God,

(Signature) Cecil M. Olson

Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of June, 1951

Dean C. Cooley  
Notary Public.

My commission expires April 29, 1953

PLUGGING  
FILE SEC-10T-21-11W  
PAGE-87-LINE-27

WELL LOG  
Christiansen #1 B  
NW NE SW Sec. 10-21-12

Started May 30, 1951  
Completed June 10, 1951

Elevation 1847 DF  
Anhydrite 624'  
Heebner 3099'  
Brown lime 3234'  
Arbuckle 3540'

0-227	Sand, rock and red bed
227-624	Red bed, sand and shale
624-661	Anhydrite
661-1560	Shale, shells and red bed
1560-1940	Shale, and sandy lime
1940-2265	Lime and shale
2265-2650	Lime and shale
2650-2950	Lime and shale
2950-3140	Lime and shale
3140-3280	Lime and shale
3280-3310	Lime
3310-3455	Lime
3455-3540	Lime and conglomerate
3540-3601	Arbuckle lime
2601	TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton SS.

I, Lynn O. Duke of the DUKE & WOOD DRILLING COMPANY, INC. being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 16 1951  
CONSERVATION DIVISION  
Wichita, Kansas

Lynn O. Duke  
Vice-President

Subscribed and sworn to before me this 14 day of June 1951.

PLUGGING  
FILE SEC 10T 21 R 12W  
BOOK PAGE 87 LINE 29

Dean L. Cooley