


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

STAFFORD County, Sec. 10 Twp. 21S Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner VIRGINIA DRILLING COMPANY  
Lease Name CHRISTIANSEN Well No. 1  
Office Address 712 BROWN BUILDING - WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) OIL  
Date well completed 19  
Application for plugging filed NOVEMBER 10 19.69  
Application for plugging approved 19  
Plugging commenced NOVEMBER 11 19.69  
Plugging completed NOVEMBER 15 19.69  
Reason for abandonment of well or producing formation DEPLETED



Locate well correctly on above  
Section Plot

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. W. WARREN  
Producing formation Depth to top Bottom Total Depth of Well 3590' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	313'	None
				5 1/2"	3588'	2782'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3590' - 3520' - SAND  
3520' - 3480' - 5 SACKS CEMENT  
3480' - 225' - MUD  
225' - BASE - PUMPED 15 SACKS MUD AND 75 SACKS CEMENT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.  
Address BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
T. L. NUTT (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
BOX 562 - GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of DECEMBER, 19 69

My commission expires JULY 31, 1970  
Mary M. Guesnier  
Notary Public.

W E L L L O G

Virginia Drilling Company, Inc.  
Christiansen "B" #1, SE SE SW  
Section 10-21S-12W  
Stafford County, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

ELEVATION: 1848' GL; 1850' DF; 1852' KB.

## FIGURES INDICATE BOTTOM OF FORMATION:


PIPE RECORD:	0	to	20	surface sand & clay
8 5/8" set @ 313'			80	sand & shale
with 225 sacks cement.			230	sand
5 1/2" set @ 3588'			643	red bed
with 100 sacks cement.			1530	shale & shells
			1780	shale & lime
			2060	lime & Shale
ROTARY COMMENCED: 7-21-69			2810	shale & shells
ROTARY COMPLETED: 7-27-69			3126	lime & shale
			3228	shale
			3590	lime & shale
			3590	Rotary Total Depth

TOPS:

Anhydrite	658
Heebner	3094
Toronto	3114
Brown Lime	3228
Lansing	3242
Arbuckle	3528

STATE OF KANSAS )  
COUNTY OF BARTON ) ss

I, W. F. Banks, Drilling Superintendent of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath declare: That I have knowledge of the facts statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

  
\_\_\_\_\_  
W. F. Banks

Subscribed and sworn to before me on this 31st day of July, 1969.

My commission expires: 7-7-72.

  
\_\_\_\_\_  
I. J. Rader, Notary Public