

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 10 Twp. 21S Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE
Lease Owner Aspen Drilling Co.
Lease Name Laudick Well No. 1
Office Address P. O. Box 783, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed September 16 19 66
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced February 11 19 69
Plugging completed February 12 19 69
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production October 29 19 68
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation Arbuckle Depth to top 3482' Bottom 3495' Total Depth of Well 3500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	257'	none
				5 1/2"	112 jts	80 jts.
Arbuckle	Oil	3482'	3495'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Rigged up and cleaned out cellar.
Sanded to 3350'. Dumped 5 sacks cement. Working pipe.
Shot pipe at 2696'. Working pipe.
Shot pipe at 2600'. Worked pipe. Shot pipe at 2505'.
Pushed plug to 240 ft., 30 ft. rock bridge. Dumped 2 sacks cement with Calcium Chloride.
Bailed hole down. Filled surface casing with 4 yards ready-mix concrete.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1969
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pawnee Drilling Company, Inc.
Address P. O. Box 783, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
John H. Volosin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Volosin, President
P. O. Box 783, Great Bend, Kansas
(Address)

Subscribed and sworn to before me this 24th day of February, 19 69
Theora Holleman, Notary Public.
My commission expires April 18, 1972.



D R I L L E R S L O G

15.185.30368.0000

COMPANY Aspen Drilling Co.
 CONTRACTOR Aspen Drilling Co.
 LEASE NAME Laudick #1
 LOCATION NE NW NE Sec.10-T21S-R12W
 Stafford County, Kansas
 ELEVATION 1860 K.B.
 SURFACE CASING 14 jts. (257') 10 3/4"
 OIL STRING 112 jts. (3494.76') 5 1/2"
 COMMENCED September 7, 1966
 COMPLETED September 16, 1966
 ROTARY TOTAL DEPTH 3500'

<u>FORMATION</u>	<u>DEPTH</u>
Clay-Sand	180
Shale	225
Red Bed	633
Anhydrite	657
Shale & Shells	1500
Limestone & Shale	1905
Limestone	2095
Shale & Limestone	2875
Limestone	3040
Limestone & Shale	3215
Limestone	3490
Arbuckle	3493
RTD	3500

Surface pipe set at 10:30 PM, 9/8/66
 14" hole to 258'. Ran 14 jts. (257')
 of 10 3/4" used casing. Set at 255'
 with 275 sx sunset.

- DST #1 - 3229 - 3240
- DST #2 - 3258 - 3275
- DST #3 - 3276 - 3302
- DST #4 - 3489 - 3495
- DST #5 - 3494 - 3500

Ran Electric log.

Ran 112 jts. (3494.76') 5 1/2" 14# J-55
 used casing set @ 3491' (2' off bottom)
 with 120 sx 50-50 light posmix, salt
 saturated, plug down at 5:40 p.m.
 9-16-66.

FORMATION TOPS

Anhydrite	633 (+1227)
Topeka	2810 (-950)
Heebner	3074 (-1214)
Toronto	3093 (-1233)
Douglas	3107 (-1247)
Brown Lime	3210 (-1350)
Lansing	3223 (-1363)
BKC	3444 (-1584)
Conglomerate	3451 (-1591)
Simpson	3462 (-1602)
Arbuckle	3482 (-1622)
Rotary Total Depth	3500 (-1635)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 13 1969
 CONSERVATION DIVISION
 Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS)
) ss:
 COUNTY OF BARTON)

The undersigned, being duly sworn on oath, states that the above statement and log are true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle

Subscribed and sworn to before me this 4th day of October, 1966.

Theora Holleman
 Theora Holleman
 Notary Public

My commission expires: April 18, 1968.