

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record  
K.A.R. -82-3-117

API NUMBER 15-185-23143-0000  
LEASE NAME McFarland "A"  
WELL NUMBER 2-11

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

430 Ft. from North Line of Section  
600 Ft. from East Line of Section

LEASE OPERATOR F.G. Holl Company, L.L.C. SPOT LOCATION 100' S & 60' E of N/2 Ne Ne  
ADDRESS P.O. Box 780167 Section 11 Township 21s Range 11w  
CITY, STATE, ZIP Wichita, Kansas 67278-0167 County Stafford  
PHONE # 316-684-8481 Date Well Completed October 21, 2001  
Character of Well Dry and Abandoned Date Plugging Commenced October 21, 2001  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed October 21, 2001

The plugging proposal was approved on October 19, 2001 at 3:30 pm (date)  
by Richard Lacey (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 3525

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	140			
Redbeds	Shale	140	235	8-5/8"	216.62'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged well on 10/21/01 using 175 sx 60/40 Poz, 6% Gel, as follows: Heavy mud in the hole to the bottom plug @ 3485' with 50sx, 2nd plug @ 660' with 50sx, 3rd plug @ 260' with 50sx and top plug @ 40' with 10sx cemented to surface, Plugged rathole with 15 sx. Job completed at 5:30 am on 10/21/01 by Allied, ticket #8558.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F.G. Holl Company, L.L.C. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 22nd day of October, 19 2001



Linda L. Stauffer  
(Notary Public)

RECEIVED

My Commission Expires: \_\_\_\_\_

OCT 24 2001

KCC WICHITA

Form CP-4  
Revised 12-92

OP

RECEIVED

OCT 24 2001

KCC WICHITA  
**Sterling Drilling Company, Rig #1**

Box 1006, Pratt, Kansas 67124-1006  
 Office Phone (316) 672-9508, Fax 672-9509

**SAMPLE LOG**

**McFarland "A" 2-11**

**LOCATION:** 100' S & 60' E of N/2 Ne Ne Section 11 T 21s R 11w  
**API:** 15-185-23143-0000 Stafford County, Kansas

**OWNER:** F.G. Holl Company, L.L.C.  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 13-Oct-01  
**COMPLETED:** 21-Oct-01

**TOTAL DEPTH:** **DRILLER**

3525
------

**FEET**  
**LOGGER**

3527
------

**FEET**

**Ground Elevation:** 1748  
**KB Elevation:** 1757

**LOG**

0 -	4 FEET	Top Sand
4 -	27 FEET	Sand and Gravel
27 -	17 FEET	Fine sand
17 -	65 FEET	Clay
65 -	90 FEET	Sand and Gravel
90 -	140 FEET	Sand
140 -	480 FEET	Redbeds
480 -	498 FEET	Anhydrite (Driller's)
498 -	980 FEET	Shales and Salt
980 -	3485 FEET	Limestone, Shale and Dolomite
3485 -	3525 FEET	Arbuckle

**CASING RECORDS**

**Surface Casing-8-5/8"**

Spud @ 8:00 am on 10/13/01. Drilled 12-1/4" hole to 235'. Ran 5 joints of new 24# 8-5/8" surface casing, tally 216.62' set at 228' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC and 1/4# Celloflake. Cement did circulate. Plug down at 1:15 pm on 10/13/01 by Acid Services.

**Plugging Report**

Plugged well on 10/21/01 using 175 sx 60/40 Poz, 6% Gel, as follows: Heavy mud in the hole to the bottom plug @ 3485' with 50sx, 2nd plug @ 660' with 50sx, 3rd plug @ 260' with 50sx and top plug @ 40' with 10sx cemented to surface, Plugged rathole with 15 sx. Job completed at 5:30 am on 10/21/01 by Allied, ticket #8558.

**DEVIATION SURVEYS**

1/4	degree(s) at	230	feet
1-1/4	degree(s) at	3342	feet
3/4	degree(s) at	3525	feet