

15.185.22535.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 185 - 22,535

LEASE NAME McFarland

RECEIVED
STATE CORPORATION COMMISSION
STATE CORPORATION

AUG 3 1988

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-11

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11 TWP. 21 RGE. 11 (E) or (W)

COUNTY Stafford

Date Well Completed 7-30-88

Plugging Commenced 12:45 AM, 7-30-88

Plugging Completed 2:15 AM, 7-30-88

CONSERVATION DIVISION
LEASE OPERATOR Kansas G. Holl Company

ADDRESS P.O. Box 780167, Wichita, KS 67678-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 29, 1988 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3465'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	305.50 KB	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fill hole with heavy mud. 50 sacks at 510'; 40 sacks at 340'; 10 sacks 0 to 40'.
15 sacks in rathole. Used 60/40 Pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address P.O. Box 129, Sterling, KS 67579


STATE OF Kansas COUNTY OF Rice, ss.

F. A. Wuellner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) F. A. Wuellner

(Address) F. A. Wuellner, Secretary
P.O. Box 129, Sterling, KS 67579

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 88



Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission Expires: 4-6-89

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- McFarland #1-11
 Located SE SE SE, Section 11-T21S-R11W, Stafford County, Kansas

OWNER: F. G. Holl Company
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 24, 1988

COMPLETED: July 30, 1988

TOTAL DEPTH: 3465'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 310	Sand	Ran 7 joints of 8 5/8" 23# new casing. 294.93' pipe set at 305.50 K.B.
310 - 325	Shale & Clay	Cemented with 250 sacks 60-40 Pozmix, 2% Gel, 3% cc. Plug down at 12:30 PM, 7-24-88, by Howco.
325 - 950	Shale	
950 - 3175	Shale & Lime	
3175 - 3385	Lime	
3285 - 3380	Lime & Shale	
3380 - 3465	Simpson & Arbuckle	Plugged.

Deviation Survey: 3/4° at 3325'

RECEIVED
 STATE CORPORATION COMMISSION

112 3 1988

CONSERVATION DIVISION
 Wichita, Kansas