

2-010101

*Rec'd
6-10-96*

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

5-2

API NUMBER: 15-159-21,590-0000

N/2 NW SEC 13 , T 21 S , R 7W

OPERATOR LICENSE # 5610

4623 FEET FROM S SECTION LINE

OPERATOR: Bruce Oil Company

3920 FEET FROM E SECTION LINE

NAME & RR 4, Box 1

LEASE NAME: C J Johnson WELL # 2-13

ADDRESS: McPherson, KS 67460

COUNTY: Rice

WELL TOTAL DEPTH: 3530' *114.72*

CONDUCTOR PIPE: _____ @ _____

SURFACE CASING: 8 5/8" @ 202'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR Sunflower Well Service, Inc.

ADDRESS: 408 N. 4th, PO Box 341, Canton KS 67428-0341 LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 2 MONTH: May YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM Lonny Bruce

COMPANY NAME: Bruce Oil Company PHONE: 316-241-2938

WERE: Sand to 3330' and top with 4 sacks cement. Shoot pipe off and pull to 950'.
Spot 35 sacks cement. Pull pipe to 300' and circulate cement to the surface.
4 1/2" casing at 3488' Perforations at 3384' to 3427'

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 16:00 DAY: 2 MONTH: May YEAR: 1996

ACTUAL PLUGGING REPORT: Sanded to 3330' and topped with 4 sacks cement. Ripped pipe
at 2900'. Pulled pipe to 953' and spotted 35 sacks cement. Pulled pipe to 331' and
circulated 147 sacks cement to the surface.
Retrieved 2900' of 4 1/2" casing (70 jts.)

REMARKS: Used 60/40 posmix with 4% gel by United - Invoice #2372

I DID OBSERVE THIS PLUGGING.

*Rec'd
6-10-96
M. Wilson*

Michael R. Wilson
Michael R. Wilson AGENT

INVOICED

DATE 6-10-96

INV. NO. 45755

DW

15.159.21590.0000

GULFCO PRODUCTION, INC.

4200 WESTHEIMER, #255

#2-13 C.J. JOHNSON

13-21-7W

657' FNL &

HOUSTON, TX 77027

1360' FWL, NW/4

CONTR DUKE DRILLING CO., INC.

CTY RICE

GEOL

FIELD WHEBRY

+	+
+	+
+	+

ELV NA

SPD 4/1/83

CARD ISSUED

6/9/83

IP OIL WELL

FORM & INTV - NA

API 15-159-21,590

Tops	Depth-Datum
TOP	2432
HEEB	2712
DOUG	2736
BR LM	2866
LKC	2878
BKC	3258
CONG	3385
MISS	3418
KIND	3488
RTD	3530

8 5/8 " 202/190SX; 4 1/2 " 3488/75SX
 MICT - CO. PF (MISS) INTV NA, SWB DWN, SO, POP - TIGHT
 HOLE - NO OTHER INFO TO BE RELEASED AT PRESENT - WILL
 RELEASE INFO WHEN AVAILABLE - TEMP COMP - 6/9/83

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 KANSAS CORP CO:AM
 1998 APR 23 A 10:52