

1 051045

5-6-88

API NUMBER 19-185-21,065 .0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW SE, SEC. 6, T 21 S, R 14 W/R  
990 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Frey "B" Well # 4

Operator: National Cooperative Refinery Assoc.  
Name & Address Box 6  
Great Bend, KS 67530

County Stafford 120.64

Well Total Depth 3712 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 883

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 6 Month: 5 Year: 19 88

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3698' Open hole 3698-3712' Elevation 1927'

1st plug sand back to 3458' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 6 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3548' and dumped 5 sx cement on top of  
sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released  
8 5/8" wiper plug and pumped 100 sx cement..

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

**INVOICED**

RECEIVED  
STATE CORPORATION COMMISSION

5-13-88

MAY 13 1988

CONSERVATION DIVISION  
Wichita, Kansas

DATE 5-17-88

Signed Richard W. Lacy  
(TECHNICIAN)

INV. NO. 20646