

To: 1 070007
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 12/50 15.185.10776.0000

SW SE SE, SEC. 6, T 21 S, R 14 XX

330 feet from S section line

990 feet from E section line

Lease Name Frey B Well / 1

County Stafford

Well Total Depth 3704 20.38 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 879

TECHNICIAN'S PLUGGING REPORT 2-14

Operator License # 30517

Operator: TURNCO Drilling Co.

Name & Address 3900 Broadway

Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 14 Month: 2 Year: 19 96

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

logs: 5 1/2" at 3691' w/75 sx cement, PBSD 3590', Perfs at 3522-29'

1st plug sand back to 3470' and dump 5 sx cement on top of sand through bailer

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 125 sx cement. 2-9-96

RECEIVED
KANSAS CORP COM
FEB 9 9 39 AM '96

Plugging Proposal Received by Bill Johnson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 14 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3470' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls, and pumped 125 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to [unclear]) observe this plugging.

DATE 2-29-96

INV. NO. 44914

Signed [Signature]
(TECHNICIAN)