

1121007

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,704-0000

NW NE SW, SEC. 32, T 21 S, R 13 W XE
2310 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

Lease Name Hufford Well # 1

Operator: Hallwood Petroleum, Inc.

County Stafford

Name & Address 4582 S. Ulster St. Pkwy, Ste. 1700
P.O. Box 378111
Denver, CO 80237

Well Total Depth 4100 133.25 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address

Company to plug at: Hour: 8 a.m. Day: 11 Month: 1 Year: 19 95

Plugging proposal received from George Hutton

(company name) Hallwood Petroleum, Inc. (phone) 316-792-2756

Work: 5 1/2" at 3900' w/200 sx cement, DV at 776', cement circulated, PBTD 3880'

1st plug cement from DV tool to surface.

Check annulus.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 11 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug ran 2 7/8" tubing to 744' and circulated 5 1/2" casing

with 55 sx cement.

2nd plug pumped in 8 5/8" X 5 1/2" annulus with 10 sx cement. Shut in at 600 psi.

RECEIVED STATE CORPORATION COMMISSION

1-18-95

1884 4 400E JAN 19 95

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

WICHITA, KANSAS

DATE 1-20-95

Signed Steve Durrant (TECHNICIAN)

INV. NO. 42087