

1 120777

3-5

15.185.01793.0002

4R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-16,179
NE NE SE, SEC. 32, T. 21 S, R. 13
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613
Operator: Hallwood Petroleum, Inc.
Name & Address: P.O. Box 378111
Denver, CO 80237

Lease Name Chapman Well # 1
County Stafford
Well Total Depth 3784 122.98 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hallwood Petroleum, Inc. License Number 3613
Address P.O. Box 378111, Denver, CO 80237

Company to plug at: Hour: 9:30 a.m. Day: 5 Month: 3 Year: 19 93

Plugging proposal received from George Hutton

(company name) Hallwood Petroleum, Inc. (phone) 316-792-2756

Perfs: 5 1/2" at 3766' w/150 sx cement, PBTD 3728', Perfs at 3462-67, 3449-53, 3419-23, 3499-3504
3537-45; 3766-84'

Clean hole, perforate at anhydrite and below salt section, and plug through tubing:
1st plug pump 25 sx gel and hulls and 25 sx cement on bottom,
2nd plug perforate at 800' and pump cement to surface through tubing, 3rd plug hook onto 5 1/2" &
circulate 8 5/8".

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 5 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT Perforated 5 1/2" casing at 770' and 2000'.

1st plug ran tubing to 3008' and pumped 25 sx gel & hulls, laid down 1 jt. of tubing and spotted
40 sx cement with hulls at 2977',
2nd plug laid down 32 jts. tubing and spotted 40 sx cement at 2030', 3rd plug laid down 39 jts.
tubing and pumped in 320 sx cement. Cement didn't circulate. 4th plug pumped in 8 5/8" X 5 1/2"
annulus with 100 sx cement. Pumping pressure 550 psi and shut in 350 psi.

RECEIVED STATE CORPORATION COMMISSION
3-10-93

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. 367' of 2 7/8" tubing & Baker Model R-1000 10ft in
No casing recovery. Additional description is necessary, use BACK of this form.) 5 1/2" casing

I (did / did not) observe this plugging.

DATE MAR 10 1993

INV. NO. 37490

Signed [Signature] (TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas