

1 080523

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,373.0000

W/2 SW NW, SEC. 8, T 21 S, R 14 (W) X

3300 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9112101 Energy & Resources Lease Name Barrett Well # 1-A

Operator: Larilou Energy & Resources, Inc. County Stafford 120.41

Name & Address 2770 Bermuda Circle Well Total Depth 3705 feet

Colorado Springs, CO 80917 Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 893'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address P. O. Box 823, Great Bend, KS67530

Company to plug at: Hour: 11:00 pm Day: 16 Month: May Year: 19 86

Plugging proposal received from Leonard Williamson

(company name) Duke (phone) 316-793-8366

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A
Anhydrite N/A

1st plug in the top of the Arubckle with 40 sx cement if 50' or more

2nd plug at 930' with 50 sx cement

3rd plug at 390' with 25 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15 am Day: 16 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 930' with 50 sx cement, 2nd plug at 390' with 25 sx

cement, 3rd plug from 40' to surface with 10 sx cement, 4th plug to circulate rat hole

with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE MAY 28 1986

INV. NO. 13996

Signed J. A. [Signature] (TECHNICIAN)

STATE CORPORATION COMMISSION
MAY 27 1986
CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 5/11/86 month day year

API Number 15-185-22,373.0000

OPERATOR: License # 9112
Name: Energy & Resources, Inc.
Address: 2770 Bermuda Circle
City/State/Zip: Colorado Springs, Colorado 80917
Contact Person: Robert Shaw
Phone: 303/574-7700

W/2 SW NW Sec. 8 Twp. 21 S, Rg. 14
3300 Ft. from South Line of Section
4950 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5929
Name: Duke Drilling Co., Inc.
City/State: Great Bend, Kansas 67530

Nearest lease or unit boundary line 330 feet
County: Stafford
Lease Name: Barnett Well #: 1-A
Ground surface elevation feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 250
Depth to bottom of usable water 250
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 250+
Conductor pipe required
Projected Total Depth 3700 feet
Formation: Arbuckle

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 4/25/86 Signature of Operator or Agent Sally R. Byers Title Agent

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt. 1 2
This Authorization Expires 10-25-86 Approved By 4-25-86

Spud 5-11-86 8:00 AM
waterwell plug from bottom to top

Set 893' sp.
Spud 5-9-84

PLUGGING PROPOSAL IF ABOVE IS D & A 10-11:00

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Top of Arbuckle 50 feet depth with 40 sxs of 60/40 Pozz. 6% gel
2nd plug @ 800-900' + 30' 930 feet depth with 50 sxs of 60/40 Pozz. 6% gel
3rd plug @ 50' below surface pipe 40 feet depth with 40 sxs of 60/40 Pozz. 6% gel
4th plug @ 40' Solid Bridge 10 feet depth with 10 sxs of 60/40 Pozz. 6% gel
5th plug @ feet depth with sxs of
(2) Rathole with 15 sxs (b) Mousehole with 15 sxs

Water Well -

NOTE: Agreement between operator and district office on plug placement and the amount of cement to be used is necessary prior to plugging.

Table with columns: PUSHER Leonard Williamson, TD FORMATION, SURFACE PIPE @, ANHYDRITE ELEVATION, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Halliburton, TECHNICIAN

RECEIVED STATE CORPORATION COMMISSION MAY 27 1986 CONSERVATION DIVISION Wichita, Kansas