

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20305-00-00  
Spot: CSESE Sec/Twnshp/Rge: 8-21S-40W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: SPURLAND A Well Number: 1-8  
County: HAMILTON Total Vertical Depth: 3300 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

Conductor Pipe: Size feet: \$ 107.25  
Surface Casing: Size 8.625 feet: 346 WITH 275 SX CMT  
Production: Size 5.5 feet: 3299 WITH 400 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/23/2002 8:20 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 5 SX HULLS FOR PLUG, 150 SX 60/40 POZ MIX W/6% GEL. PRESSURE UP ON BACK-SIDE (8-5/8" X 5-1/2") & PUMP 50 SX DOWN ANNULUS IF NECESSARY.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/23/2002 9:05 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 3299'. PERFS AT 2770-82'. PUMPED DOWN 5 1/2" 500# HULLS & 225 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 800#. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 25 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 500#.

RECEIVED  
JAN 31 2002 1-31-02  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin Strube  
(TECHNICIAN)

INVOICED JAN 29 2002  
DATE Feb 1-02  
INV. NO. 2002061326

Form 08-2/3