

9-27

I 020179

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,311-0000
C NE SE, SEC. 7, T 21 S, R 23 W/EX

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
660 feet from E section line

Operator License # 5068

Lease Name Brady Well # 1

Operator: Thomas E. Black d/b/a

County Hodgeman 145.76

Name & Address Black Petroleum Company

Well Total Depth 4485 feet

P.O. Box 12922

Conductor Pipe: Size feet

Wichita, KS 67277

Surface Casing: Size 8 5/8 feet 297

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Box 819, Russell, KS 67665

Company to plug at: Hour: 11:30 p.m. Day: 26 Month: 9 Year: 19 88

Plugging proposal received from Tom Allum

(company name) Emphasis Oil Operations (phone) 913-483-5345

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1505-38'

1st plug at 1510' with 50 sx cement, 2nd plug at 650' with 50 sx cement,

3rd plug at 330' with 40 sx cement, 4th plug at 40' with 10 sx cement.

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:45 a.m. Day: 27 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1520' with 50 sx cement,

2nd plug at 650' with 50 sx cement,

3rd plug at 350' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

(SEE / d / note) observe this plugging.

INVOICED

DATE 10-4-88

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 22438

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1988

CONSERVATION DIVISION
Wichita, Kansas