

1052373

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-20,391-0000
W/2 NE NW SEC. 13, T 21 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WRIGHT WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 119.93

OPERATOR LICENSE # 6170

WELL TOTAL DEPTH 3690 FEET

OPERATOR: GLOBE OPERATING, INC.

PRODUCTION CSG: SIZE 5 1/2" @ 3688' WITH 150 SX

NAME AND PO BOX 12

SURFACE CASING: SIZE 8 5/8" @ 286' WITH SX

ADDRESS GREAT BEND, KS 67530-0012

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530-0628

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 22 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RALPH STALCUP

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 3478-83

CASING COLLAPSED AT 430'. RAN TUBING TO 413'. PUMPED CEMENT DOWN TUBING CIRCULATING UP

5 1/2" AND 8 5/8". TOTAL OF 135 SX. PULLED TUBING. PUMP 115 SX CEMENT DOWN 5 1/2" CASING.

MAXIMUM PRESSURE 150 PSI. SHUT IN PRESSURE 100 PSI.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:05 PM DAY: 22 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

CASING COLLAPSED AT 430'. RAN TUBING TO 413'. PUMPED CEMENT DOWN TUBING CIRCULATING UP

5 1/2" AND 8 5/8". TOTAL OF 135 SX. PULLED TUBING. PUMPED 115 SX CEMENT DOWN 5 1/2" CASING.

MAXIMUM PRESSURE 150 PSI. SHUT IN PRESSURE 100 PSI.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

RECEIVED STATE CORPORATION COMMISSION

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) FEB 28 2000

I (DID) OBSERVE THIS PLUGGING

INVOICED

DATE 2/28/00

SIGNED

Richard M. Lacy
(TECHNICIAN)

CONSERVATION DIVISION
Wichita/Kansas
FORM CP 12/3

WV. REG. 06/30/6

R