

1030675

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,246-0000

C NE NE, SEC. 7, T 21 S, R 23 W/E XX

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4808

Lease Name Brady Well # 41-7

Operator: Smokey Oil Company

County Hodgeman 146.58

Name & Address P. O. Box 2360

Well Total Depth 4510 Mississippi feet

Casper, WY 82602

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 441

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor True Drilling Company License Number 4708

Address P. O. Drawer 2360, Casper, WY 82602

Company to plug at: Hour: 11:00 am Day: 12 Month: March Year: 19 86

Plugging proposal received from Buzz Montgomery

(company name) True (phone) 307-237-9301

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2277' Anhydrite 1495'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 900' with 50 sx cement

3rd plug at 450' with 40 sx cement

4th plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:00 pm Day: 12 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1515' with 50 sx cement, 2nd plug at 900' with 50 sx cement, 3rd plug at 450' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

3-20-86

MAR 20 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton (if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

MAR 20 1986

Signed Steve Durrant (TECHNICIAN)

DATE

INV. NO. 13038

3-12 APR 10 1986

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date March 14 1986 month day year

API Number 15-083-21,246-0000

OPERATOR: License # 4808 Name Smokey Oil Company Address P. O. Box 2360 City/State/Zip Casper, WY 82602 Contact Person C. F. Pickard Phone (307)-266-0230

C NE NE Sec. 7 Twp. 21S S. Rg. 23 East West 4620 Ft. from South Line of Section 660 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 4708 Name True Drilling Company City/State Casper, WY 82602

Nearest lease or unit boundary line 660 feet County Hodgeman Lease Name Brady Well # 41-7 Ground surface elevation 2277 feet MSL Domestic well within 330 feet: yes no Municipal well within one mile: yes no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 200 Depth to bottom of usable water 420 Surface pipe planned to be set 420 Projected Total Depth 4450 feet Formation Mississippian

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.

Date Feb. 12, 1986 Signature of Operator or Agent C. F. Pickard Title Engineer

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 420 feet per An. This Authorization Expires 8-18-86 Approved By 2-18-86

Spud 3-5-86 Sit 420'

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 50 sx Base Anhydrite feet depth with 40 sx of 2nd plug @ 50 sx 30' below base surf. feet depth with 1/2 50 sx - 1710 sx of 3rd plug @ 10 sx 40' below surf. feet depth with 40 sx - 40 sx of 4th plug @ 15 sx in rat. hole feet depth with 10 sx - 10 sx of 5th plug @ feet depth with sx of (2) Rathole with 10 sx

PUSHER Billy Anderson TD 4510 FORMATION MISS SURFACE PIPE 878 441 ANHYDRITE 1495 ELEVATION 2277 STARTING TIME & DATE wed. 3-12-86 COMPLETION TIME & DATE 2:00 3-12-86 1st PLUG @ 1515 FT. W/ 50 SX 2nd PLUG @ 900 FT. W/ 50 SX PLUG @ 450 FT. W/ 40 SX 4th PLUG @ 40-0 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ 10 SX CEMENT COMPANY Hall, best TECHNICIAN

1st 1500' w/ 50 sx. 2nd 900' w/ 50 sx. 3rd 450' w/ 40 sx. 4th 40-10 10-10 MAR 20 1986 CONSERVATION DIVISION Wichita, Kansas