

15.185.00239.0000

Form CP-3
Rev. 6-4-68

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Spector Pipe & Supply Co. Inc.

Complete Address Box 169 Russell, Ks 67665

Lease Name Fry B (FREY "B") Well No. 3

Location C N/2 NE/SE Sec. 6 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3701

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ralph Lynch Casing Pulling Co.

Address Rt. 4 Great Bend, Ks License No. 457

Operation Completed: Hour 11:00 AM Day 5 Month 7 Year 1972

The above well was plugged as follows:

877 ft 8 5/8 surface pipe cemented with 400 sacks. 3690 ft 5 1/2 long
string cemented with 150 sacks. Open hole. Sand back to 3350 ft,
5 sacks cement with bailer. Pulled 2500 ft 5 1/2. Pump 2 sacks hulls,
15 sacks gel, 100 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Handwritten Signature*
Well Plugging Supervisor

INVOICED

DATE 7/7/72

INV. NO. 6002-W