

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 67-13

LOCATION SW-71E-SE

SEC. 32 TWP. 21 RGE. 17-4

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Chapman

Operator Mr. Francis Raymond Address #202 Bismark Bldg - Wichita - Kans.

Field _____ County Stafford

Total Depth 3890 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 200 ft. Circulated with cement.
7" casing set at 3889 ft. Cemented with 100 sacks cement.
Low Wells Plug at 3790 ft. Filled hole with sand from
3780 to 3510 ft. Dumped 6 sacks of cement at 3510 ft.
Shot of x pulled the 7" casing. Mud to 200 ft. Set Rock
Bridges & 20 sacks of cement at 200 ft. Mud to 30 ft.
Plug x 10 sacks of cement at the surface.
Advert casing pulling Co. Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION

APR - 4 1951

CONSERVATION DIVISION
District Conservation Agent

Date 4-2-51

PLUGGING
FILE SEC 32 TWP 21 R 17-4
BOOK PAGE 67 LINE 33