

15-009-03329-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Duke Drilling Company

Complete Address: Box 823, Great Bend, Kansas 67530

Lease Name Soskopf Well No. # 4 Twin

Location App. SE SW SE Sec. 21 Twp. 16 Rge. 12 (E) (W) W

County Barton Total Depth 3387

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 11:30 AM Day 27 Month 5 Year 1969

The Above well was plugged as follows:

8 5/8" 327' C_{wc}.

Sanded hole back to 3320' & dumped 5 sax cement with dump bailer. Pulled pipe.

Mud to 310', set 10' rock bridge, & displaced 5 sax cement. Let set over night.

Bailed hole dry & displaced 20 sax cement. Mud to 40', set 10' rock bridge, & displaced 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don L...
Well Plugging Supervisor

DATE 6/2/69
INV. NO. 9870-u