

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 6720215-009-06551-00-00
(S W D)
API Number 15 - - (of this well)Operator's Full Name John Jay Darrah, Jr.Complete Address 1010 Century Plaza, Wichita, Kansas 67202Lease Name Steskeof Well No. 3 SWDLocation NW NW SE Sec. 21 Twp. 16 Rge. 12 (E) (W) XCounty Barton Total Depth 3500'Abandoned Oil Well Gas Well Input Well SWD Well X D & A Other well as hereafter indicated Plugging Contractor John Jay Darrah, Jr. & Allied Cementing Co.Address 1010 Century Plaza, Wichita, Kansas License No. Operation Completed: Hour 1:15 PM Day 13 Month 2 Year 1980

The above well was plugged as follows:

Squeezed thru 5 $\frac{1}{2}$ " casing with 50 sx cement, 1 sx hulls,50 sx cement, 1 $\frac{1}{2}$ sx hulls, 10 sx mud gel, $\frac{1}{2}$ sx hulls,and 200 sx cement.Filled to bottom of celler with 3 $\frac{1}{2}$ yards of ready mix cem.No casing recovery.Squeezed at 325' with 225 sx cement, circulated3452' of 5 $\frac{1}{2}$ " casing cemented with 200 sx cement.325' of 3 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 2-15-80Inv. NO: 1536 wRECEIVED
FEB 15 1980
CONSERVATION DIVISION
Wichita, Kansas

File copy

WELL LOG

Date Started: November 11, 1957
Date Completed: November 23, 1957

Stoskopf No. 3 15-009-06551-00-00
NW SW SE
Section 21-16-12
Barton County, Kansas

Elevation	1912'	K.B.
Anhydrite	812'	(+1100)
Heebner	2998'	(-1086)
Brown Lime	3087'	(-1175)
Lansing	3104'	(-1192)
Base Kansas City	3346'	(-1434)
Conglomerate	3362'	(-1450)
Arbuckle	3402'	(-1490)
R.T.D.	3500'	(-1588)

8 5/8" set at 325'
5 1/2" set at 3452'

10'	-	40'	Surface Clay and Sand
40'	-	80'	Shale
80'	-	90'	Sand
90'	-	110'	Shale
110'	-	130'	Sand
130'	-	250'	Shale
250'	-	275'	Sand
275'	-	315'	Sand and Shale
315'	-	330'	Shale
330'	-	495'	Blue Shale
495'	-	765'	Red Bed
765'	-	812'	Red Bed and Shale
812'	-	836'	Anhydrite
836'	-	1350'	Shale and Shells
1350'	-	1740'	Shale and Shells
1740'	-	1885'	Shale and Lime
1885'	-	1990'	Shale and Lime Streaks
1990'	-	2170'	Lime and Shale
2170'	-	2565'	Lime and Shale
2565'	-	2730'	Lime and Shale
2730'	-	2935'	Lime
2935'	-	2998'	Lime
2998'	-	3104'	Heebner
3104'	-	3346'	Lansing
3346'	-	3402'	Lime
3402'	-	3500'	Arbuckle
3500'	-		R.T.D.

RECEIVED
STATE OF KANSAS DEPARTMENT OF COMMISSION

JUN 2 1979

RECEIVED
STATE OF KANSAS DEPARTMENT OF COMMISSION

AFFIDAVIT

State of Kansas County of Barton

I, Cecil M. Olson, employee of the owner, do swear that the statements and matter herein contained are true to the best of my knowledge.

THE DUKE DRILLING COMPANY

BY: _____

Subscribed and sworn before me this 29th day of November, 1957.

NOTARY PUBLIC

My commission expires: June 24, 1959.