

15-009-30268-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1968
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Frank J. Black

Complete Address: Box 150 McPherson, Kansas

Lease Name Norton Well No. 4

Location S/2 SW SW Sec. 21 Twp. 16 Rge. 12 (E) (W) X

County Barton Total Depth 3406

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 10 A Day 15 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 3406' 8 5/8 csg set at 330' cwc

5 1/2 csg 3382' cw 75 sx cmt.

Filled 5 1/2 csg with sand to (3370-3406) and dumped 5 sc cmt. with dump bailer (3330-3370)

Cutoff and recovered 2868' of 5 1/2 csg.

Mud to 330' set rock bridge (315-330) Cemented with 25 sc cmt. (240-315)

Mud to 40' set rock bridge (35-40) Cemented with 10 sc cement. (0-35)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. W. F. Massey
Well Plugging SupervisorDATE 8/16/68
INV. NO. 8291-4