

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials or signature

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____
LOCATION SW NW NW
SEC. 13 TWP. 21 RGE. 14 W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Wright 710 Ketter Bldg
Operator Armer Drg Co, Inc. Address Wichita, Kans
Field _____ County Stafford
Total Depth 3689 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 266' circulated with cement - 5 1/2" at 3687' with
150 sax cement behind. Lane Wells plug to 3675', top perf
at 3488', filled with chat to 3480', set 5 sax cement with
dump bailer, pulled 5 1/2", filled hole with mud to 250', set
rock bridge and 15 sax cement, filled with mud to 35', set
rock and 10 sax cement to bottom cellar.

STATE COM.

MAY 10 1951

CONSERVATION DIVISION
Wichita, Kansas

John T. Kelly
District Conservation Agent

Date 5-8-51

PLUGGING
FILE SEC. 13 T 21 R 14 W
BOOK PAGE 81 LINE 1