


KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

MAR 14 1966

CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Western Petroleum Company, Inc.
 Complete Address: 925 Patton Road, Great Bend, Kansas
 Lease Name Wright Well No. # 1
 Location NW SE NW Sec. 13 Twp. 21 Rge. 14 (E) (W) W
 County Stafford Total Depth 3785'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated:
 Plugging Contractor: Forbes Casing Pulling, Inc.
 Address: Box 221, Great Bend, Kansas License No. 49
 Operation Completed: Hour 11:00AM Day 11th Month March Year 1966

The Above well was plugged as follows:

274' of 8 5/8" surface pipe, cemented with 225 sacks. 3690' of 5 1/2" long
string, cemented with 100 sacks. Plug back TD 3681'. Top perferation
3423'. Bottom of the hole was sanded to 3400', and cemented with 5 sacks.
3014' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 270', rock bridge from 270' to 260', 10 sacks of cement
was mixed in a barrel, and put on plug at 260', through the dump bailer, and
let set over-night. Next morning hole was bailed dry, and 15 sacks of cement
was added to the plug. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
 Well Plugging Supervisor

DATE 3/14/66
 INV. NO. 2852-W