

State of Kansas



15.185.01455.0000

FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts.
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

NOV 18 1963
11-18-63
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Jesse Drury of Prime Drilling Co. has this

date requested permission to plug the following described well:

Mr. Drury guarantees payment of the plugging fee.

Operator's full Name: C. H. Spoor Jr.

Complete Address: 1078 N. Armour Lane, Wichita, Kansas

Lease Name: Hullett Well No. # 1

Location: C N/2 SE Sec. 11 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3700 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Drury was instructed to plug the well as follows:

278' of 8 5/8" surface pipe, cemented with 250 sacks.

Fill hole with drilling mud to 275', 1st cementing plug,

1/4 sack hulls, cement with 25 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement

with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent