

State of Kansas



15-009-01255-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1968
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ervin Brack of Duke Drilling Company has this
date requested permission to plug the following described well:

Mr. Pipe Pullers, Inc. guarantees payment of the plugging fee.

Operator's full Name: Duke Drilling Company

Complete Address: Box 823, Great Bend, Kansas 67530

Lease Name: Stoskopf Well No. # 1

Location: SE/4 Sec. 21 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3420 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ben Thompson was instructed to plug the well as follows:

8 5/8" 301' Cwc.

Sanded hole back to 3340' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mud to 300', set 10' rock bridge, & displaced 5 sax

cement. Let set over-night, bailed yole dry, & displaced 20 sax

cement. Mud to 40', set rock bridge, & displaced 10 sax cement, cement-

ing to base of cellar.

Very truly yours,

Don L. Lusk
Conservation Division Agent