

State of Kansas



15-009-03329-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 2 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Ervin Brack of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Pipe Pullers, Inc. guarantees payment of the plugging fee.

Operator's full Name: Duke Drilling Company

Complete Address: Box 823, Great Bend, Kansas 67530

Lease Name: Stoskopf Well No. # 4 Twin

Location: App. SE SW <sup>SE</sup> Sec. 21 Twp. 16 Rge. 12 (E)(W)W

County: Barton Total Depth 3387 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Ben Thompson was instructed to plug the well as follows:

8 5/8" 327' Cwc.

Sanded hole back to 3320' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mud to 310', set 10' rock bridge, & displaced 5 sax cement.

Let set over night. Bailed hole dry & displaced 20 sax cement. Mud to

40', set 10' rock bridge, & displaced 10 sax cement, cementing to base

of cellar.

Very truly yours,

Don L. Linn  
 Conservation Division Agent