

15.185.23159.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

RECEIVED
JUL 26 2002
KCC WICHITA

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-23159-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: F.G. Holl Company, L.L.C. KCC LICENSE # 5056
(owner/company name) (operator's)

ADDRESS: P.O. Box 780167 CITY: Wichita
STATE: Kansas ZIP CODE: 67278-0167 CONTACT PHONE: 316-684-8481

LEASE: H. Debes WELL#: 1-8 Section 8 Township 21s Range 14w
40' S of Nw Sw SPOT LOCATION/QQQQ COUNTY: Stafford

1940 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)
620 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT NA CEMENTED WITH NA SACKS
SURFACE CASING SIZE 8-5/8" SET AT 857' KB CEMENTED WITH 210 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1931 G.L. 1940 K.B. T.D. 3775 P.B.T.D. _____ Anhydrite Depth 821
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Received plugging orders 07/23/02 from Steve Middleton. Plugged on 07/24/02 in following manner;
135 sx of 60/40 Poz, 6% Gel; Heavy mud in hole and between all plugs. Bottom plug at 3686'-40 sx.
2nd plug at 880'-50 sx. 3rd plug at 230'-20 sx. Top plug at 40'-10 sx cemented to surface.
Rathole-15 sx. No mousehole. Plug down at 1:00 pm on 07/24/02. Acid Services ticket #4866.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes _____ (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Gary Pugh /Gary Talbott Phone#: (316) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 1:00 pm on July 24, 2002. 1:00 pm

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 07/24/02 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator