

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-083-21,372.0000 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Bankoff Oil Company OPERATOR'S LICENSE NO. 6040

ADDRESS 100 S. Market, #203A, Wichita, KS 67202 PHONE # (316) 262-2784

LEASE (FARM) Brady WELL NO. #1 WELL LOCATION NW NW SE COUNTY Hodgeman

SEC. 7 TWP. 21S RGE. 23 (E) or  (W) TOTAL DEPTH 4466' PLUG BACK TD         

**Check One:**

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO.         

SURFACE CASING SIZE 8 5/8" SET AT 314.81' CEMENTED WITH 60-40 posmix-190 sx SACKS

CASING SIZE          SET AT          CEMENTED WITH          SACKS

PERFORATED AT         

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 1530' w/50 sx; 2nd plug @ 750' w/50 sx; 3rd plug @ 350' w/50 sx; 4th plug @ 40' w/10 sx; rathole 15 sx; 60-40 posmix 1/4# Flocel per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?          IS ACO-1 FILED? no  
(If not explain.) Sent to Operator to complete.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12:00 a.m. 12-7-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 ~~et seq.~~ AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:         

Tony Martin PHONE # (913) 743-5443 1-21-92

ADDRESS P.O. Box 294, Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton  
(Operator or Agent)

DATE: January 7, 1992

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 21 1992  
CONSERVATION DIVISION  
Wichita, Kansas