

*Q*

Form CP-3  
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 23 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed July 11, 1967

Operator's Full Name Rains & Williamson Oil Company, Inc.

Complete Address 1425 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Love Well No. # 1

Location NE SE NE Sec. 31 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3860'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Rains & Williamson Oil Company, Inc.

Address 1425 Wichita Plaza Bldg., Wichita, Kansas License No.       

Operation Completed: Hour 12:00 A.M. Day 22nd Month August Year 1967

The above well was plugged as follows:

288' of 8 5/8" surface pipe, cemented with 275 sacks. 100 sacks of cement  
with 50-50 Poz Mix and 6% Gel was spotted at 540', through the drill pipe,  
with cement from 540' to 240'. Hole was filled with drilling mud to 40',  
bridge plug bridged with 1/2 sack of hulls on fluid at 40', and cemented  
with 10 sacks, with cement from 30' to the base of the cellar. Rat hole  
bridged and cemented with 5 sacks.

This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 8-23-67

INV. NO. 6193-W