

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 009-07431-00-00 (of this well)

Operator's Full Name Palamino Petroleum

Complete Address 500 Insurance Bldg., Wichita, Kansas 67202

Lease Name Christians Well No. 4

Location C W/2 NE SE Sec. 20 Twp. 16 Rge. 12 (X) (W) X

County Barton Total Depth 3388'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc

Address Box 128, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 10:45 AM Day 14 Month 6 Year 1978

The above well was plugged as follows:

Sanded back to 3340' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 3 sx hulls,

25 sx mud gel, 2 sx hulls, and 100 sx cement.

Max. pres. 500#. Shut in pres. 150#.

Recovered 2535' of 5 1/2" casing.

3372' of 5 1/2" casing cemented with 75 sx cement.

373' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

6-20-78

INV. NO.

1509. W

Signed: Donald Rankin

Well Plugging Supervisor